

Client: EBC Capital		GSF 126,840		GSF 126,840	
Trade Code / Description		COST w/ CCIP	\$ / GSF	Cost w/ Insurance	\$ / GSF
01.3504.00 Site Security		309,569	2.44	309,569	2.44
01.3508.00 Temp Site Utility Usage		88,788	0.70	88,788	0.70
01.3528.00 Site Safety / Fire Safety Manager		771,060	6.08	771,060	6.08
02.2000.00 Site work		1,080,972	8.52	1,174,970	9.26
02.4100.00 Demolition		701,081	5.53	701,081	5.53
02.6001.00 Asbestos Abatement		By Owner		By Owner	
03.3001.00 Concrete on Deck		417,232	3.29	468,800	3.70
03.3100.00 Superstructure Concrete / Insulated Concrete Forms		1,525,068	12.02	1,713,560	13.51
04.2100.00 Masonry / EIFS / Restoration		1,319,626	10.40	1,450,138	11.43
05.1200.00 Structural Steel		2,207,169	17.40	2,373,300	18.71
05.5001.00 Miscellaneous Metal		963,780	7.60	1,036,323	8.17
06.1001.00 Drywall / Miscellaneous Carpentry		799,203	6.30	854,763	6.74
07.5001.00 Roofing / Pavers / Waterproofing		1,639,415	12.93	1,801,555	14.20
07.8100.00 Fireproofing		Excluded		Excluded	
07.9200.00 Sealant		74,400	0.59	74,400	0.59
08.1200.00 Doors, Frames & Hardware (furnish only)		44,260	0.35	44,260	0.35
08.4200.00 Entrance / Storefronts / Louvers		543,536	4.29	563,250	4.44
08.5001.00 Curtain Wall		567,420	4.47	588,000	4.64
08.8001.00 Interior Glazing		7,334	0.06	7,600	0.06
09.3100.00 Tile, Terrazzo and Stone		50,879	0.40	55,303	0.44
09.6800.00 Carpet / Vinyl Flooring/ VCT		24,158	0.19	25,700	0.20
09.9100.00 Painting & Wallcovering		174,249	1.37	188,377	1.49
10.1400.00 Signage		60,775	0.48	65,000	0.51
10.2800.00 Toilet Partitions & Accessories		27,633	0.22	30,200	0.24
10.8001.00 Miscellaneous Specialties & Equipment		20,708	0.16	20,708	0.16
11.1200.00 Automated Parking		Excluded		Excluded	
11.3001.00 Appliances		Excluded		Excluded	
11.9001.00 Window Washing Equipment		Excluded		Excluded	
14.2001.00 Elevators & Escalators		561,600	4.43	585,000	4.61
14.8001.00 Hoist and Sidewalk Bridge		1,188,419	9.37	1,291,760	10.18
21.1300.00 Fire Protection System		873,870	6.89	955,049	7.53
22.1100.00 Plumbing		608,676	4.80	665,220	5.24
22.4001.00 Plumbing Fixtures - Allowance		36,000	0.28	36,000	0.28
23.2001.00 HVAC Sheet metal and Piping		2,385,719	18.81	2,524,570	19.90
26.0800.00 Electrical		2,645,948	20.86	2,785,208	21.96
26.5001.00 Lighting Fixtures - Allowances		385,400	3.04	385,400	3.04
31.1001.00 Excavation / Foundation		2,123,689	16.74	2,359,654	18.60
32.3001.00 Landscaping / Hardscaping / Irrigation		Excluded		Excluded	
50.9900.00 Fit-Out Allowance (incl's finishes, casework, trim, etc.)		250,000	1.97	250,000	1.97
50.9901.00 Winter Heat - Allowance		0	-	0	-
Total Trade Cost		\$24,477,636	\$192.98	\$26,244,566	\$206.91
Estimating / Design Contingency	10.00%	\$2,447,764		\$2,624,457	
Subtotal		\$26,925,399	\$212.28	\$28,869,022	\$227.60
Subcontractor Default Insurance (% of Trade Cost - Excluding Winter Heat / Site Safety/Security & Site Utility)	1.75%	\$407,894		\$438,815	
Subtotal		\$27,333,293	\$215.49	\$29,307,837	\$231.06
General Conditions (% of Trade Cost)	9.00%	\$2,423,286		\$2,598,212	
Subtotal		\$29,756,579	\$234.60	\$31,906,049	\$251.55
CCIP Insurance (% of Trade Costs & GC's)	8.75%	\$2,353,831		\$0	
Subtotal		\$32,110,410	\$253.16	\$31,906,049	\$251.55
GL Insurance Allowance (% of Trade Cost & GC's)	2.75%	\$0		\$793,176	
Subtotal		\$32,110,410	\$253.16	\$32,699,226	\$257.80
Professional/ Pollution Insurance Allowance	0.25%	\$67,252		\$72,107	
Subtotal		\$32,177,662	\$253.69	\$32,771,333	\$258.37
Construction Contingency (% of Trade Cost & GC's)	5.00%	\$1,345,046		\$1,442,139	
Subtotal		\$33,522,708	\$264.29	\$34,213,471	\$269.74
C.M. Fee (% of Trade Cost, GC's, Cons. Cont.)	3.50%	\$988,609		\$1,059,972	
Total Cost Summary		\$34,511,317	\$272.09	\$35,273,443	\$278.09

QUALIFICATIONS:

1. Estimate based on Building Statistics – Conceptual Layouts dated 10/23/18 (Architect Not Listed) & Structural Progress set dated 12.10.18 from RAS P.E. Consulting Engineers.
2. Current Estimate is a Conceptual Budget Estimate.
3. Project is a 3 story Production Studio & Office Area Building / Garage Structure with a Mezzanine Level.
4. Foundations are figured as a 6" SOG (No Cellar) – based on 50% of total area – balance existing slab to remain in place
5. A Continuous footing at the perimeter / interior high wall / high bay wall and garage wall is included. An 18" thick frost wall is carried at the perimeter.
6. A Pile allowance is based on the RAS P.E. 12.10.18 drawing on 100' Deep per Pile (4 Piles Per Cap as shown on drawing)
7. Contaminated Soil Remediation is excluded.
8. Tie Backs, Rock Excavation & Rock anchors are excluded.
9. The building Structure consists of Precast Double-Tee at the Parking Garage / Office building Portion as shown on the 12.10.18 RAS P.E. Drawing. The main stage area is Structural Steel Joist system with Metal Decking & Concrete Topping for the Roofing system with clear span and trusses.
10. Structural Steel framing @ Stage Roof is figured as 10lbs per Sq/Ft Long Span Joist High Bat @ 6' O.C. as shown on the RAS P.E. 12.10.18 Drawing.
11. Spray-on-Fireproofing is excluded.
12. This project would assume use of a Mobile crane that would have insurance as part of the allowance.
13. Building Permit and Filing Fees are not included.
14. Preconstruction Precondition Surveys are excluded.
15. An Estimating & Design Contingency has been included.
16. Optical monitoring is excluded.
17. Excludes Owner's Contingency.
18. Excludes costs for Preconstruction.
19. Excludes moving costs.
20. Builders Risk Insurance is not included (Owner to provide).
21. Railroad Insurance is not included.
22. LEED Management, Design, & LEED Construction costs are excluded.
23. MTA/Amtrak Permits, Filings, Fees, Flag Men, Surveys, or other Costs or Documentation are excluded.
24. Excludes Expeditor's costs other than those required for DOT permit, and after hours work variances.
25. Final cleaning is not included final broom clean is included.
26. Exterior and Interior Window cleaning is excluded.

27. Excludes Land Acquisition Fees, Realty Taxes, etc.
28. Ground Water Treatment is not included.
29. Unforeseen conditions are not included.
30. Removal of Underground Obstructions or Predrilling for Piles are not included.
31. Excludes Independent Inspection Agency Services and Controlled Inspections. (By Owner)
32. Excludes Geotechnical surveys and borings.
33. Construction Managers' Bond is excluded.
34. Vibration monitoring, video cameras at adjacent buildings and/or required by City Agencies are excluded.
35. Sewer Discharge Fees are Excluded
36. FF&E and Artwork is excluded.
37. Audit costs are excluded.
38. Removal of any existing property violations is excluded.
39. Audits on insurance and any associated additional costs are excluded.
40. Excludes Terrorist insurance.
41. Move-in standby costs or removal of tenant rubbish is not included.
42. Prevailing wage labor is excluded.
43. Budget is based on use of Capital Improvement certificate provided by owner
44. Budget is based on current building code. Any changes potentially required by 2018 code are excluded.
45. Escalation is not included, based on today's pricing market.
46. Excludes potential Tariffs.
47. Excludes responsibility for delays associated with Union Actions – effort will be made to continue working, however delays associated with Union actions beyond our control shall not be the responsibility of Leeding Builders Group.
48. All items identified as "Allow" or "Allowance", within the budget, shall be considered monies allotted for that particular work item. If the actual value is less than that allowance the net savings shall be returned to the Owner. Likewise if the actual value exceeds the allotted allowance a change order shall be issued by the Owner to cover the overage, along with associated markup / fees.

TRADE ITEMS:

1. Excludes overtime costs other than those required to maintain Project Schedule.
2. Costs associated with delays caused by the Municipal Authorities are not included.
3. Excludes Mock-ups and Laboratory testing.
4. Gas service work or meters outside of property limits are excluded.
5. DEP Landfill requirements are not included.
6. Excludes work outside site other than new utility services into building.
7. Utility relocations are excluded.
8. Commissioning Agent or any associated costs are not included.
9. Costs associated with Site Utility Usage are excluded.
10. Localized dewatering is excluded.
11. Bathroom finishes are assumed Porcelain tile material for all Bathrooms.
12. Vinyl Base and Carpet for Office Production Corridors.
13. Stage Area Insuquilt Blankets full-height on the all walls at the provided material allowance of \$3 per Sq/Ft.
14. Purlin Grid, for attaching stage lights, is included at an allowance of \$75,000 per stage.
15. Elevators: One 3,000# Car and One 5,000# Car are included.
16. Lighting Fixtures are included as allowances
17. Façade Assumptions:
 - a. Louvered System for Parking Garage Façade
 - b. Curtain Wall System @ Office Production (Street Side Façade)
 - c. Exterior Insulation Façade System on CMU for Office Walls Facing Roof Area, exterior of the stage bldg. above the existing brick facade and Bulkhead
18. Roofing System is TPO with 10% Allowance of Roof Area for Mechanical Walkway Pads 24x24x1/4"
19. MEPS System is based on 1 Ton / 150 sf for the Stage Areas with 1,600A 3 Phase per Studio & Extra Hazard Class 2 fire suppression system at the Stage Areas. Rooftop Units at the Office Spaces with 400A 3 Phase per floor.
20. Life Safety 300 KW Generator is included.
21. Professional Kitchen Equipment is excluded (none shown).
22. Automated Parking Systems are excluded (none shown).
23. Window Washing Equipment is excluded (none shown).
24. Furnishing, Handling or Installation of any Retail / Theater / Stage / Equipment is not included.
25. Excludes future tenant work letter.

-
- 26. DOT Road Repair associated with the Federally Funded Highway Program is excluded.
 - 27. After Hour Permits, including cost of site safety manager, are excluded.
 - 49. Fit-Out Allowances are included and shown in Allowance section below.

ALLOWANCES

The following allowances have been included in our Estimate Dated December 17, 2018:

Purlin Grid for Lighting attachment @ Stage Area	\$ 75,000 Per Stage
Mechanical Walkway Pads – Allow 24"x24"x1/4"	\$ 12 Per S/F
Door Hardware - Common/Service	\$ 400 Per Door
Entrance Canopy Metal & Glass @ Main Entrance	\$ 70,000 Allow
Entrance Canopy Metal & Glass @ Stage Room Entrances	\$ 20,000 Allow
Curtain Wall	\$ 120 Per S/F
Architectural Louvers	\$ 75 Per S/F
Bulkhead Louvers	\$ 70 Per S/F
Bathroom Mirror @ Public Bathrooms	\$ 1,000 Each
Porcelain Tile Material	\$ 6 Per S/F
Carpet F&I	\$ 45 Per Sq/Yd
Code Signage	\$ 25,000 Allow
Photo Luminescent Signage	\$ 20,000 Allow
Garage Signage	\$ 20,000 Allow
Public Bathroom Accessories Per Bathroom	\$ 2,500 Each
Metal Locker's	\$ 10,000 Allow
Public Restroom Fixtures	\$ 750 Each
Site Lighting	\$ 25,000 Allow
Exterior Lighting Allowance	\$ 25,000 Allow
Garage Lighting	\$ 3 Per S/F
Security Lighting Allowance	\$ 15,000 Allow
Elevator Lobby Lighting Allowance	\$ 2,000 Each Floor
Lobby Lighting Allowance	\$ 10 Per S/F
Stage Area Lighting Allowance	\$ 2 Per S/F
Millwork Shop Lighting Allowance	\$ 6 Per S/F
Common Area Lighting Allowance	\$ 50,000 Allow
Lobby – Fit Out	\$ 250 Per S/F
Intercom / CCTV / Access Controls	\$ 1.50 per GSF
Low Voltage Data Devices & NIDS	\$ 1.50 per GSF