

Conceptual Budget

555 Johnson Avenue

EBC Capital

R1 Partial Site Re-Use, January 11,2019**Schedule of Values**

Division	Trade Description	Division Totals	Cost / Sqft	Notes
Core & Shell - Studios Only				
2-000	EXISTING CONDITIONS SUBTOTAL	1,525,000	25.00	
	Demolition Work			
	Utility Work - (Excludes New Services)			
	Earthwork / Piles			
3-000	CONCRETE / PRECAST - SUB TOTAL	2,078,519	34.07	
	Piles at Precast Structure			
	Precast Superstructure			
	Slabs/Foundations			
4-000	MASONRY - SUB TOTAL	765,000	12.54	
	CMU Walls			
5-000	STEEL - SUB TOTAL	1,905,000	31.23	
	Structural Steel			
	Misc. Metals			
6-000	WOOD & PLASTICS - SUB TOTAL	77,156	1.26	
7-000	THERMAL & MOISTURE/F.PROOFING - SUB TOTAL	1,860,000	30.49	
	Sprayed Fireproofing - Studio Only			
	Waterproofing at Foundations/Roof Pavers			
	Expansion Joint Assemblies at Building to Remain			
	EIFS			
	Roof Pavers			
	Roofing			
8-000	DOORS AND WINDOWS - SUB TOTAL	36,000	0.59	
	Doors/ Frames/Hardware			
	Exterior Glass/Glazing/Storefront			
	Overhead/Elephant Doors			
9-000	FINISHES - SUB TOTAL	108,500	1.78	
	Painting/Coating at Exterior			
10-000	SPECIALTIES - SUB TOTAL	25,000	0.41	
	Fire Extinguishers			
	Laminated Lockers			
	EQ/AC and AP Specialties			
11-000	EQUIPMENT - SUB TOTAL	-	0.00	
	-			
12-000	FURNISHINGS - SUB TOTAL	-	0.00	

Conceptual Budget

555 Johnson Avenue

EBC Capital

R1 Partial Site Re-Use, January 11,2019



Schedule of Values

Division	Trade Description	Division Totals	Cost / Sqft	Notes
14-000	ELEVATORS & LIFTS - SUB TOTAL	-	0.00	
	Elevators and Lifts			
15-000	MECHANICAL - SUB TOTAL	1,200,000	19.67	
	Fire Protection (Sprinkler)			
	Plumbing			
	HVAC			
16-000	ELECTRICAL - SUB TOTAL	1,530,000	25.08	
	Service			
	Electrical			
	Fire Alarm			
	Construction Sub Total	\$ 11,110,174	182.13	
17-000	GENERAL CONDITIONS			
	Pre-Construction Services			
	Staffing			
	Reimbursables			
	General Conditions Sub Total	\$ 989,100	16.21	
18-000	INSURANCES/FEES/BONDS			
	Construction Contingency			Excluded
	Overhead and Profit			
	Builder's Risk Insurance			Excluded
	Subcontractor Default Insurance			(In lieu of Bonding)
	Contractors Liability Insurance			
	General Requirements - Insurance & Fee	\$ 998,190.11	16.36	
	Core & Shell Total Construction Budget	\$ 13,097,464	214.71	
Fit Out Sub Totals per the Scope of Work Letter				
	Studio Space & Accessory Rooms	4,148,000		
	Restrooms			Modified to Fit Out Exist Bldg
	Restrooms			Modified to Fit Out Exist Bldg
	Production Offices			Modified to Fit Out Exist Bldg
	Lots 25 & 37 Renovation & Fitout - 23,000 sqft x 1 Floor	2,760,000		
	Lots 42 Renovation & Fitout - 10,000 sqft x 3 Floors	4,050,000		
	Fit Out Sub Total	\$ 10,958,000	103.57	
	Core & Shell + Fit Out Grand Total	\$ 24,055,464	178.19	
Add Alternates & Deducts				
	1. Add 1 Floor to Lot 25 & 37	\$ 9,450,000	8.92	(Reinforce & Core&Shell)

Project Timeline

555 Johnson Avenue

EBC Capital

R1 Partial Site Re-Use, January 11, 2019



PRELIMINARY PROJECT TIMELINE

Design Kick-off through Construction / TCO

<u>TASK</u>	<u>START</u>		<u>FINISH</u>
1. CM Service Agreement – Start Pre-Construction	2/4/19	to	2/15/19
2. DD/30% CD – Document Review	3/18/19	to	3/29/19
3. Prepare Prelim schedule & bid list for early trades	4/1/19	to	4/12/19
4. DD/30% CD – Prepare budget	4/15/19	to	5/3/19
5. (Option 1. Demo Set, Bidding and Award Demolition –Nov. 2019)	5/6/19	to	5/17/19
6. (Option 2. Building Demolition –Dec, 2019)	6/3/19	to	6/28/19
7. Test pits and additional borings	7/8/19	to	7/19/19
8. CDs Issued for Excavation/SOE/Foundation	8/19/19	to	8/30/19
9. Bidding of Excavation/SOE/Foundation – Updated Dwgs	9/2/19	to	9/13/19
10. 60% CD's Issued and Budgeted	9/16/19	to	9/27/19
11. Award SOE, Excavation, Underpinning/Shoring, Foundation	9/30/19	to	10/15/19
12. Mobilize and Commence Demo/SOE/Excavation/Underpinning/Shoring (PAA to be filed with DOB for updated and final DWG)	10/21/19	to	11/29/19
13. 90% CD's issued by the design team	11/11/19	to	11/29/19
14. Bidding of all major trades	12/2/19	to	12/20/20
15. Establish GMP	1/6/20	to	1/31/20
16. Award of Major Trades	2/3/20	to	2/28/20
17. Foundation construction (2 months)	3/2/20	to	5/1/20
18. General Construction - Core/Shell (6 months)	5/4/20	to	12/4/20
19. General Construction - Existing Structures (7 months)	3/2/20	to	12/4/20
20. General Construction Misc Fit Out Thru TCO	12/4/20	to	12/31/20
21. Tenant Possession Date	12/31/20		

